The Steel Beam Guardrail Cell Library has been updated.

The following updates were made to the steel beam guardrail cell library:

- Minor changes to the cell names and descriptions
- Addition of lines representing the top, outside edge of surfacing behind the guardrail
- Addition of green placement points to some of the guardrail transitions to concrete end blocks to help with placement on the most common end block configurations

Reminder: When placing a guardrail transition on an end block, check the appropriate structure plans to determine the correct cell placement point to use. The location of the 5 bolt insert will dictate placement of the guardrail transition. The guardrail transition cells have 1, 2 or 3 possible placement points due to the various end blocks in use. The default placement point (cell origin) may not be the correct one to use.

The updated Steel Beam Guardrail Cell Library file may be downloaded from **here**.